Smock Alley Theatre Main Space Technical Specification

Get in/Out

Access

Exchange Street

Glass doors 2300mm x 1350. Green delivery door. 2260mm x 1240mm Auditorium door DSL 2000mm x 1000mm

Cows Lane

Load-in doors: 2600mm high x 2.200mm wide

Stage

Stage Depth: 7500mm from back wall to front row seating

Stage Width: 12000mm at the widest point upstage and 9950mm at the

seating downstage.

Ceiling height: 5485mm Grid trim height: 4250mm

Rigging

Grid 4 motorised trusses (LX)

FOH 1 2 Fixed IWB's FOH 2 2 Fixed IWB's

Drapes 1 spilt curtain (back wall)

Loose equipment 10 stage weights

Access equipment 1 Zarge

1 small zarge

2 x wooden A frames

Dimmers

ETC Sensor rack, housing 2 x 48x CEM+Module located behind the stage.

96 x 3kw channels in total

All circuits are 16amp

48 over the stage

6 channels on the floor upstage right

6 channels on the floor upstage left

12 channels Foh 1

12 channels Foh 2

6 channels over the audience stage right.

6 channels over the audience stage left.

Lighting desk

ETC ION located at the top of the auditorium stage right.

Lamp Stock	
RJ Fresnel	12
RJ PC	8
Strand Preludes 28/40	14
Selecon Aurora 1 K	10
S4 Pars	16
S4 Profile 15/30	12
S4 Profile 25/50	6
Quartet F (Black)	26

Talkback

Canford tecpro Master Station MS721 with 6 belt packs and headsets.

Sound

Desk Allen & Heath ilive R72. Located at the top of the auditorium

stage right

Amps 2 x Yamaha p3500 for the PA

Speakers 2 Martin x AQ12's (FOH)

2 Martin Audio Blackline S18 Bass Bins (subs)

2 martin LE 1200 Series (Mon)

Management Allen & Heath iDR-out Audio Output Expander

Martin Audio AQX system controller (crossover)

Stage boxes iDR-16 stage box at the control position

16/8 stage box upstage right

Hot power x 8 2 points upstage right floor level

1 point upstage left floor level

1 point centre LX 1
1 point stage left LX 2
1 point stage left LX 3
1 point for the sound desk

1 point above FOH 1

General information

Wheelchair access is from Exchange Street Lower through the glass doors at Kaplan's Lane.

Facilities

4 dressing rooms.

Washing machine and tumble dryer backstage Green room with a fridge, kettle and microwave.

2 toilets back stage.

2 showers back stage

Induction loop hearing aid.

A member of Smock Alley Theatre's technical staff is on site at all times but does not form part of the get in crew. We do not provide sound engineers, lighting technicians or stage management for the running of the shows or rehearsal.

A risk assessment should be furnished to the Technical Manager before the get in. Failure to notify any risk associated with the production will result in a possible refusal of that item or action as a part of the show

Get in time is 10am until 10pm for the purpose of load in, tech and rehearsals.

David Halpin Technical Manager Smock Alley Theatre